BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No.EE/YNK-D/E-PMT/08/2016-17 Dated: 4-03-2017

APPROVED TENDER SCHEDULE –'B'

Item No: 04

Name of Work:-:-construction of Drain at Gandhinagara Opposite to MEC School in ward No-01 of Yelahanka Sub Division.

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri BHASKAR K	
				Rate	Rate in Words
1	KSRB 2-2.1 : **Earth work excavation** for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, **in ordinary soil** not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications, specification, No, KBS 2.1(a) / 2.3.5, No.5/Item No. 2.3)	Cum	168.00	200.34	Rupees two hundred and paise thirty four only
2	KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregate /sand/kaner/ Moorum KSRRB M100-1 Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications MORTH -100/ Chapter 1 (Page No.133/ Item No 17.1)	Cum	168.00	89.00	Rupees eighty nine only
3	KSRB 4-1.3: Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.Specification No.KBS 4.1, 4.2 (P.12/I.4.3)	Cum	21.00	4360.00	Rupees four thousand three hundred sixty only
4	KSRB 4.9.2: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 -do- TMT Bars Fe 500 P.17/It.No.4.46.2	tonne	2.9498	57000.00	Rupees fifty seven thousand only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri BHASKAR K	
				Rate	Rate in Words
5	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.21 (P.15 / I.4.31)	sqm	336.00	310.58	Rupees three hundred ten and paise fifty eight only
6	Providing & laying in position reinforced cement concrete of Design mix M20 with OPC cement @ 320kgs , with 20mm and down size graded granite metal,coarseaggregated @ 0.69cum ,and fine aggregated @ 0.460cum, with superplastisiser @ 3lts confirming to IS9103-1999 Reaffirmed -2008 machine mixed concrete laid in layers not exceeding 15 crns thick, vibrated for all works in foundation for footings,pedestals,retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts,struts, buttresses, bed blocks, anchor blocks, plinths etc.,including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement as per specifications.specifications No.KBS 4.1,4.6 (P.No.13/ I.No.4.11)	cum	46.20	6371.66	Rupees six thousand three hundred seventy one and paise sixty six only
7	Providing and fixing **RCC precast Slabs of 0.10 m thick of CC 1:2:4 with 20 mm** and down size graded granite metal , machine mixed , including cost of all material , labour , HOM of Machinery , curing complete	sqm	126.00	1765.00	Rupees one thousand seven hundred sixty five only

K. Bhaskar
Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.